# APPENDIX B PROPOSED BEE CANYON GREENERY COMPOSTING OPERATION AT FRB LANDFILL MITIGATION MONITORING AND REPORTING PROGRAM

Mitigation Measure	Implementing Action	Method of Verification	Timing of Verification	Verification Responsibility	Date Completed
	Aesthetics	, 011110W01011	, 011110001011	1100001101101	Complete
(Aesthetics MM-1) For the water tanks that will be located on the composting site operations area, OC Waste & Recycling will ensure that the water tanks are either painted tan or a similar color or that when the tanks are ordered they will either be tan or a similar color that will blend in with the adjacent topography to reduce any aesthetics/viewshed impacts to residents using Portola Springs Community Park or to any other residents that are able to see the water tanks. In addition, the tanks will be painted with non-reflective paint.	Permit by LEA	Verification by OCWR Composting Facility Superintendent	Prior to construction (ordering the water tanks) or during construction (painting the water tanks)	OCWR	

While the Mitigated Negative Declaration-Initial Study did not identify the following environmental topics as having significant environmental impacts, in order to further reduce the less than significant impacts for these environmental topics, OCWR has added the following Project Design Features and Operational Control Measures (PDF & OCM). All of these Project Design Features and Operational Control Measures included in this Mitigation Monitoring and Reporting Program will be incorporated into the Report of Composting Site Information (RCSI), to be reviewed and approved by the Orange County Health Care Agency, Environmental Health Division, acting in its capacity as the Orange County Solid Waste Local Enforcement Agency (LEA) for the California Department of Resources Recycling and Recovery (CalRecycle). The RCSI is the key engineering, permitting, construction and operations document that the LEA will rely upon when issuing the Solid Waste Facility Permit for the Bee Canyon Greenery Composting Operation.

Air Quality – Dust Control								
(Air Quality-Dust Control PDF & OCM-1) Compost	Issuance of Solid	Verification by	During	OCWR				
windrows will not be turned during high wind episodes	Waste Facility	OCWR	operations					
exceeding wind speeds of 30 miles per hour in order to manage	Permit by LEA	Composting						
dust particulates.		Facility						
		Superintendent						
(Air Quality-Dust Control PDF & OCM-2) The compost	Issuance of Solid	Verification by	During	OCWR				
operation entryway and often-traveled paths will be overlain	Waste Facility	OCWR	construction and					
with crushed rock or asphalt to prevent tracking of onsite	Permit by LEA	Composting	operations					
materials and dust off-site.		Facility						
		Superintendent						
(Air Quality-Dust Control PDF & OCM-3) Unpaved roads	Issuance of Solid	Verification by	During	OCWR				
shall be watered as necessary to minimize visible dust.	Waste Facility	OCWR	construction and					
Alternatively, roads may be paved.	Permit by LEA	Composting	operations					
		Facility						
		Superintendent						

(Air Quality-Dust Control PDF & OCM-4) The composting	Issuance of Solid	Verification by	During	OCWR	
operation will implement SCAQMD's Rule 403, requiring	Waste Facility	OCWR	construction and		
control of fugitive dust during construction and operations via	Permit by LEA	Composting	operations		
best-available control measures. These measures include the		Facility	operations		
following:		Superintendent			
Tonowing.		Superintendent			
<ul> <li>Apply non-toxic chemical soil stabilizers according to manufacturers' specifications to all inactive construction areas (i.e., previously graded areas inactive for 10 days or more).</li> </ul>					
<ul> <li>Water active sites at least twice daily (locations where grading is to occur shall be thoroughly watered prior to earthmoving).</li> </ul>					
Cover all trucks hauling dirt, sand, soil, or other loose materials, or maintain at least 2 ft. (0.6 meter) of freeboard (vertical space between the top of the load and the top of the trailer) in accordance with the requirements of California Vehicle Code Section 23114.					
<ul> <li>Pave construction access roads at least 100 feet (30 meters) onto the site from the main road.</li> </ul>					
<ul> <li>Reduce traffic speeds on all unpaved roads to 15 mph or less.</li> </ul>					
	Air Quality - Odor (	Control			
(Air Quality-Odor Control PDF & OCM -1) The composting	Issuance of Solid	Verification by	During	OCWR	
operation will only accept green waste loads for composting	Waste Facility	OCWR	operations		
that have already been processed off-site (i.e., chip, ground and	Permit by LEA	Composting			
screened) to remove contamination such as food waste prior to		Facility			
the processed green waste being delivered to the Bee Canyon		Superintendent			
Greenery. Pre-processing will reduce the potential for highly					
odorous loads.					
(Air Quality-Odor Control PDF & OCM-2) Upon acceptance	Issuance of Solid	Verification by	During	OCWR	
at the composting operation, prior to unloading, any highly	Waste Facility	OCWR	operations		
odorous loads will be taken to the landfill working face for disposal.	Permit by LEA	Composting Facility Superintendent			
	J	Supermicinatif			

(Air Quality-Odor Control PDF & OCM-3) Upon acceptance at the composting operation, if any highly odorous loads are inadvertently unloaded, OCWR will collect the loads and take the material to the landfill working face for disposal.  (Air Quality-Odor Control PDF & OCM-4) Green waste	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent Verification by	During operations  During	OCWR OCWR	
will be delivered to the composting operation on an as-needed basis to reduce green waste odors.	Waste Facility Permit by LEA	OCWR Composting Facility Superintendent	operations		
(Air Quality-Odor Control PDF & OCM-5) OCWR will not select or use any additives or amendments in the composting operation that are either highly odorous by themselves, are highly odorous when added to the compost piles, or are highly odorous over time during the active or curing phases of the composting operation.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	
(Air Quality-Odor Control PDF & OCM-6) OCWR will comply with SCAQMD Rules 1133 and 1133.3 for green waste composting.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	
(Air Quality-Odor Control PDF & OCM-7) Incoming pre- processed materials will be stored on-site no longer than 48 hours. PGM and processed agricultural material will be loaded into a dump truck by a front loader as soon as possible and delivered to the active composting area, where the material will then be placed into new compost piles by a front loader.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	
(Air Quality-Odor Control PDF & OCM-8) The feedstock materials will be formed into elongated piles/open windrows, with dimensions not exceeding 12 feet in height, 20 feet in length and 100 feet long for composting with the addition of moisture as needed by the on-site water truck. Newly constructed compost windrows will initially be covered with at least 6 inches of finished compost within 24 hours of formation as required by SCAQMD Rule 1133.3. For the first 15 days after initial windrow formation, within six hours before turning, water will be applied as necessary to ensure the pile meets the wetness criteria described in Rule 1133.3. During this period, the temperature of each compost pile will be taken every day.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	

(Air Quality-Odor Control PDF & OCM-9) Active compost shall be maintained under aerobic conditions at a temperature of 55 degrees Celsius (131 degrees Fahrenheit) or higher for the Process to Further Reduce Pathogens (PFRP) period of 15-days or longer as specified in 14 CCR 17868.3(b)(3) utilizing wheeled loaders or a windrow turner. During the period when the compost is maintained at 55 degrees Celsius (131 degrees Fahrenheit) or higher, there shall be a minimum of five turnings of the windrow.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	
(Air Quality-Odor Control PDF & OCM-10) OCWR has prepared an Odor Impact Minimization Plan (OIMP) for the proposed composting operation in compliance with 14 CCR 17863.4. The OIMP is included as Appendix E to the Mitigated Negative Declaration for the composting operation. All odor control measures included in the OIMP are hereby incorporated into this Mitigation Monitoring and Reporting Program. Per the OIMP, each operating day, designated site personnel shall assess and evaluate the perimeter of the composting operation area and landfill boundary for objectionable odors. Best management practices (BMPs) and good housekeeping measures will be implemented to minimize the release of objectionable odors. BMPs include:  O Maintaining adequate heat in the piles through appropriate pile density, limiting turning frequency and/or pile dimensions.  Provide adequate moisture throughout the active composting process.  Frequent monitoring of temperature and moisture content assures composting conditions are within acceptable parameters.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	
Good housekeeping measures that will be implemented include:					
<ul> <li>Clearing spilled materials between windrows.</li> </ul>					
Eliminating areas with the potential for ponding water.					

		1	1			
0	Maintaining reasonably sized stockpiles of incoming feedstock by deploying it into windrows within 72 hours.					
(Air O	quality-Odor Control PDF & OCM-11) The OIMP	Issuance of Solid	Verification by	During	OCWR	
	s that OCWR implement the following steps in the event	Waste Facility	OCWR	operations	OCWR	
	bjectionable odors are detected at the composting	Permit by LEA	Composting	operations		
operation		Termit by EEA	Facility			
operation	on site.		Superintendent			
0	Stop all operations if they are causing off-site odor impacts until the source of the odors is identified, corrected and the odor migration ceases.		Supermendent			
0	Designated site personnel shall investigate likely source of odors.					
0	Designated site personnel shall determine wind patterns and direction at the time odor was detected.					
0	Based on the intensity of odor nuisance, designated site personnel shall determine if odor has travelled offsite by surveying the perimeter of the composting facility and vicinity of potential off-site receptors.					
0	If the source of odors is found to be the composting operation, determine if on-site management practices (e.g., mixing odiferous materials with sawdust or other bulking agent, turning the windrows less frequently, remove odiferous materials and dispose of them in the landfill, etc.) could remedy any odor problems and immediately take steps to remedy the situation.					
0	Determine whether or not the odor has moved off-site and if so, if it significant enough to warrant contacting the adjacent neighbors and/or the LEA.					
0	If it has been determined that odor has moved off-site, the incident shall be recorded in the compost daily operational logbook which shall include all actions and activities taken to resolve or minimize odor nuisance for future reference and operational considerations.					

MITIGATION MA	JIII OKIII G III I	D REI ORTING	INOGNIM		
o Do not start operations again (i.e., accepting additional					
green waste in temporary storage area, placement and					
formation of new windrows) until the wind and					
meteorological conditions are favorable and will not					
promote off-site odors.					
(Air Quality-Odor Control PDF & OCM-12) Per the OIMP,	Issuance of Solid	Verification by	During	OCWR	
the following complaint response protocols will be	Waste Facility	OCWR	operations		
implemented:	Permit by LEA	Composting	1		
	,	Facility			
o All odor complaints received from potential receptors		Superintendent			
and/or regulators shall be recorded in the facility		1			
operational logbook and complaint log.					
17					
o Designated site personnel shall contact complainant					
and/or regulator to obtain details of the complaint such					
as name, time, location and nature or characteristics of					
odors.					
o Designated site personnel shall notify appropriate					
regulators of the complaint.					
1					
o Designated site personnel shall investigate and					
implement methods in assessing odor impacts.					
o Designated site personnel shall immediately					
implement additional or appropriate measures to					
minimize odors.					
o Once the OIMP measure or measures have been					
implemented and the odor has been minimized,					
designated site personnel shall follow up with					
complainant.					
(Air Quality-Odor Control PDF & OCM-13) The FRB	Issuance of Solid	Verification by	During	OCWR	
Landfill maintains an on-site meteorology station that monitors	Waste Facility	OCWR	operations		
wind direction, wind speed, temperature, and relative humidity.	Permit by LEA	Composting	operations.		
Data from this station will be used to help monitor conditions at	2 22 22 2	Facility			
the composting operation if an odor issue arises and also prior		Superintendent			
to an odor issue occurring.		Superintendent			
to an odor issue occurring.					
	l .	l	J	ı	

(Air Quality-Odor Control PDF & OCM-14) For the composting operation, OCWR will establish contingency plans for operating downtime (e.g., equipment malfunction, power outage).  (Air Quality-Odor Control PDF & OCM-15) OCWR shall	Issuance of Solid Waste Facility Permit by LEA  Issuance of Solid	Verification by OCWR Composting Facility Superintendent Verification by	During operations  During	OCWR OCWR
post telephone numbers at the entrance of the composting facility to allow members of the public to contact the OCWR composting facility superintendent to report odor complaints.	Waste Facility Permit by LEA	OCWR Composting Facility Superintendent	operations	
(Air Quality-Odor Control PDF & OCM-16) Should processed green material arrive at the composting operation with noticeable odors, options for reducing odors would include but are not limited to the following: reject highly odorous loads and landfill the material; eliminate troublesome or contaminated feedstocks; mix materials upon receipt (i.e., to increase material porosity); stockpile bulking agents or high carbon amendments; make smaller piles; blanketing odorous material with a six inch to one-foot layer of bulking agent, high carbon amendments or finished compost.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR
(Air Quality-Odor Control PDF & OCM-17) Should processed green material in the temporary unloading and storage area begin to generate odors, options for reducing odors would include but are not limited to the following: expedite material processing; first in, first out processing; reduce the size of material stockpiles; blanketing odorous material with a six inch to one-foot layer of bulking agent, high carbon amendments or finished compost; reduce the volume of incoming materials; identify alternative facilities for incoming materials.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR
(Air Quality-Odor Control PDF & OCM-18) Should processed green material begin to generate odors during mixing and material handling, options for reducing odors would include but not be limited to the following: create windrow piles that are sufficiently blended; combine materials to achieve a high carbon to nitrogen ratio (greater than 30 to 1); create piles with good porosity; ensure that mixing areas/activities are located as far as possible from sensitive receptors; reduce mixing/materials handling activity during stagnant air conditions; reduce mixing/materials handling activity when	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR

		THE SKILLS	INGGILINI		
wind is in the direction of sensitive receptors; mist water or					
odor neutralizer at dust generation points.	T CG 1' 1	XX 10' 1	Б.	OCIVID	
(Air Quality-Odor Control PDF & OCM-19) Should	Issuance of Solid	Verification by OCWR	During	OCWR	
processed green material begin to generate odors during the	Waste Facility		operations		
composting process, options for reducing odors would include	Permit by LEA	Composting			
but not be limited to the following: turn regularly to re-		Facility			
invigorate the composting process; maintain sufficient moisture		Superintendent			
in windrows; avoid over-watering windrows; make smaller					
windrows to increase passive aeration; increase porosity and bulk density; consider blanketing odorous materials with a six-					
inch to one-foot layer of bulking agent; make piles on a one-					
foot bed of overs to increase airflow; reduce turning/material					
handling activities when winds are blowing in the direction of					
nearby receptors; diligently manage and monitor the					
composting process.					
(Air Quality-Odor Control PDF & OCM-20) Should	Issuance of Solid	Verification by	During	OCWR	
processed green material begin to generate odors during	Waste Facility	OCWR	operations		
screening, options for reducing odors would include but not be	Permit by LEA	Composting			
limited to the following: reduce screening activities during		Facility			
stagnant air conditions; reduce screening activities when wind is		Superintendent			
in the direction of nearby receptors; use mist water or					
neutralizer at dust generation points.					
(Air Quality-Odor Control PDF & OCM-21) Should	Issuance of Solid	Verification by	During	OCWR	
processed green material begin to generate odors from water	Waste Facility	OCWR	operations		
ponding after a rain event, options for reducing odors would	Permit by LEA	Composting			
include but not be limited to the following: inspect piles after		Facility			
major rain events; grade the site to eliminate puddles,		Superintendent			
depressions and wheel ruts where water collects; absorb ponded					
water with wood chips/other absorbent, fill potholes with					
soil/pad material.	Y 60 111	XX 10 .1 1	ъ .	OCIVID	
(Air Quality-Odor Control PDF & OCM-22) Should	Issuance of Solid	Verification by	During	OCWR	
processed green material begin to generate odors after as a	Waste Facility	OCWR	operations		
result of uncomposted material in aisles between the windrows,	Permit by LEA	Composting			
options for reducing odors would include but not be limited to		Facility			
the following: clean aisles of spilled material (particularly at the		Superintendent			
end of each day; mechanically sweep paved areas at the end of					
each shift; apply water and/or neutralizer to reduce dust during					
dry conditions.					

WITHOUT IN					
(Air Quality-Odor Control PDF & OCM-23) Should		Verification by	During	OCWR	
processed green material begin to generate odors during curing,	Waste Facility	OCWR	operations		
options for reducing odors would include but not be limited to	Permit by LEA	Composting			
the following: increase processing time prior to moving to		Facility			
curing; decrease curing pile size; review moisture content of in-		Superintendent			
process compost; aerate curing piles; screen after curing to					
maintain porosity.					
(Air Quality-Odor Control PDF & OCM-24) Should	Issuance of Solid	Verification by	During	OCWR	
collected leachate and storm water in the lined pond begin to	Waste Facility	OCWR	operations		
generate odors, options for reducing odors would include but	Permit by LEA	Composting	1		
not be limited to the following: review NPDES procedures to		Facility			
minimize storm water contact with organic materials; remove		Superintendent			
particles from water draining into the lined pond; filter					
stormwater through a filter berm or sock; clean out lined pond					
during the dry season; reapply collected leachate and storm					
water to active compost piles; install aeration system.					
Hazards and Hazardous	   Materials	us Waste Exclusion	and Control	L L	
(Hazards and Hazardous Materials – Hazardous Waste	Issuance of Solid	Verification by	During	OCWR	
Exclusion and Control PDF & OCM-1) The existing	Waste Facility	OCWR	operations	OCWK	
hazardous waste exclusion and load-checking program for the	Permit by LEA	Composting	operations		
FRB Landfill will also be used for the proposed composting	Fernit by LEA	Facility			
operation. Loads are inspected both at the fee booth and during		Superintendent			
unloading. If any hazardous materials are discovered in loads at		Superimendent			
the fee booth, the hauler will be turned away from the landfill					
and provided with information regarding acceptable hazardous					
waste disposal facilities. Any hazardous wastes that are					
discovered after unloading, if safe to handle, will be stored at					
the temporary hazardous waste storage area at the landfill,					
before being transported off-site by a certified hazardous waste					
hauler for proper disposal.					
Hazards and Hazardous					
(Hazards and Hazardous Materials - Exclusion of		Verification by	During	OCWR	
Unacceptable Solid Wastes PDF & OCM-1) For the	Waste Facility	OCWR	operations		
composting operation, all green waste materials received will be	Permit by LEA	Composting			
processed, ground and screened prior to delivery to the		Facility			
composting operation. This will eliminate most non-green		Superintendent			
waste solid waste materials prior to delivery to the composting					
operation. However, if contaminated loads are received at the					
composting operation that contain food wastes or other					
unacceptable solid wastes, these loads will be immediately					

	JNII OKING ANI	D KEI OKIII (G	INOUNAM		
collected and transported to the landfill working face for					
disposal.					
	dous Materials – Fire				
(Hazards and Hazardous Materials-Fire Prevention and Protection PDF & OCM-1) OCWR shall provide fire prevention, protection and control measures, including, but not limited to, temperature monitoring of windrows and piles, adequate water supply for fire suppression, and the isolation of potential ignition sources from combustible materials. A strip of sufficient width of cleared land must be maintained along the perimeter of site operations to act as a fire barrier or break. OCWR will consult with OCFA to determine the size of the fire break.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	
(Hazards and Hazardous Materials-Fire Prevention and Protection PDF & OCM-2) The composting operation will be designed and operated to meet all Orange County Fire Authority (OCFA) fire flow and fire safety requirements. This will include but not be limited to the spacing between windrows; the number, width and length of fire lanes; the distance of the windrows and material storage areas to flammable vegetation, a water tank, water pumps, water lines and fire hydrants.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	
(Hazards and Hazardous Materials-Fire Prevention and Protection PDF & OCM-3) All 20-foot wide compost pile areas will be surrounded by 20-foot wide fire access lanes. Perimeter roads will be a minimum width of 20 feet and expand to a minimum width of 40 feet at hydrant locations to accommodate fire response.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During operations	OCWR	
	Hydrology and Water	· Quality			
(Hydrology and Water Quality PDF & OCM-1) Prior to construction of storm water containment and treatment facilities and prior to grading of the composting operation project site, OCWR shall prepare a Storm Water Pollution Prevention Plan ("SWPP) to obtain coverage under the State-wide general construction storm water pollution National Pollutant Discharge Elimination System ("NPDES") permit. The BMPs outlined in the SWPPP shall be implemented in project construction and operations.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	Prior to construction	OCWR	

WILLIGATION MC	71 121 O111 1 O 111 12	J REI ORTHIO	1110 0111111	,	
BMPs are used to control surface water runoff, erosion and					
siltation at the project site during the construction of the					
proposed facility. Typical BMPs are listed below:					
- Fuel delivery or dispensing will be observed by facility personnel. Fuel delivery or dispensing that is not observed by					
facility personnel is prohibited.					
racinty personner is promoted.					
- Vehicles and equipment will be kept in good working order.					
Equipment and vehicles with leaks are to be repaired promptly					
by trained mechanics.					
- Equipment and parts with a potential to impact storm water					
are to be placed under tarps as needed during storm events.					
- Spills will be reported and proper spill response procedures					
will be promptly implemented. Should such a situation occur,					
soils affected by spills and leaks from landfill equipment will be					
removed. Proper clean-up procedures will first involve removal					
of the impacted soil layer. The soil will then be placed in 55-					
gallon drums for off-site treatment and disposal.					
- Berms, silt fences, sandbags, hay bales, wittle-wattles, geo-					
logs and straw mats will be installed during construction to					
reduce erosion.					
- BMPs include both non-structural and structural controls.					
Non-structural controls will include BMPs such as preventative					
maintenance, proper materials handling, spill prevention and					
control and litter control. Structural controls would include					
BMPs such as overhead coverage, secondary containment, roof					
gutters, paved surfaces designed to maintain positive drainage					
and curbs.	Y 60 111	XX 'C' 1	D : .	OCHID	
(Hydrology and Water Quality PDF & OCM-2) Prior to	Issuance of Solid	Verification by	Prior to	OCWR	
operation of the composting operation, OCWR shall apply for coverage under the State-wide general storm water NPDES	Waste Facility Permit by LEA	OCWR Composting	operations		
permit for industrial facilities or apply for an individual facility	Termit by LEA	Facility			
storm water NPDES permit.		Superintendent			
r		1			

(Hydrology and Water Quality PDF & OCM-3) OCWR	Issuance of Solid	Verification by	During	OCWR	
shall conduct quarterly sampling and testing of windrow	Waste Facility	OCWR	operations	OCWR	
leachate and runoff for the presence of any hazardous	Permit by LEA	Composting	operations		
substances at concentrations above those effluent standards set	Termit by ELLT	Facility			
forth in the project's NPDES permit.		Superintendent			
(Hydrology and Water Quality PDF & OCM-4) OCWR shall	Issuance of Solid	Verification by	During	OCWR	
fully contain all surface water runoff and leachate resulting	Waste Facility	OCWR	operations	OCWK	
from the composting operation. Collected surface water runoff	Permit by LEA	Composting	operations		
and leachate will be collected on-site from the composting	Termit by EEA	Facility			
operation lined pond, and reused with the composting operation.		Superintendent			
(Hydrology and Water Quality PDF & OCM-5) Testing of	Issuance of Solid	Verification by	During	OCWR	
finished compost (i.e., after the curing process is complete) for	Waste Facility	OCWR	operations	oe w K	
pathogens, metals and physical contamination will be	Permit by LEA	Composting	operations		
performed in accordance with California Code of Regulations	Termit by ELLT	Facility			
Title 14 requirements.		Superintendent			
(Hydrology and Water Quality PDF & OCM-6) Although	Issuance of Solid	Verification by	During	OCWR	
OCWR has no plans to use additives or amendments as part of	Waste Facility	OCWR	operations	oe wit	
the composting operation at this time, should this change in the	Permit by LEA	Composting	- F		
future, any additives or amendments that will be used shall be	1 2111111 0 1 2211	Facility			
non-toxic and subject to the approval of the RWQCB and the		Superintendent			
LEA prior to their use.		~ · · · · · · · · · · · · · · · · · · ·			
(Hydrology and Water Quality PDF & OCM-7) For the Bee	Issuance of Solid	Verification by	During	OCWR	
Canyon Greenery, the site will be graded such that the center of	Waste Facility	OCWR	operations		
each compost pile will be located on a high point and the	Permit by LEA	Composting	1		
compost deck will be graded at 2 percent toward the access		Facility			
lanes which will be graded at 2 percent to the northeast, as		Superintendent			
shown on <b>Figure 5</b> , conveying flows to an approximate 15.84-		•			
acre feet lined composting operation pond, that will be					
constructed to capture storm water runoff and leachate from the					
composting operation. The composting operation lined pond					
dimensions were determined based on National Oceanic and					
Atmospheric Administration (NOAA) precipitation data based					
for a 25-year, 24-hour storm event (per Order WQ 2015-0121-					
DWQ, General Waste Discharge Requirements for Composting					
Operations) and the appropriate tributary boundary of the					
compost area. In addition, in accordance with standard					
engineering practices, the pond will be designed to					
accommodate an additional two feet of freeboard above the					
water level of the design storm event to accommodate waves					
and splashing from water flows.					

Noise Control							
(Noise Control PDF & OCM-1) Construction activities will be limited to between the hours of 7:00 a.m. and 7:00 p.m. on weekdays and between the hours of 9:00 a.m. and 6:00 p.m. on Saturdays. The County of Orange shall have the discretion to permit construction activities to occur outside of the allowable hours if compelling circumstances warrant such an exception (e.g., weather conditions to pour concrete).	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During construction	OCWR			
(Noise Control PDF & OCM-2) Construction contractors shall limit haul truck deliveries to the same hours specified for construction equipment (between the hours of 7:00 a.m. and 7:00 p.m. on weekdays and between the hours of 9:00 a.m. and 6:00 p.m. on Saturdays (except in the case of urgent necessity)). The contractor shall prepare a haul route exhibit for review and approval by OCWR prior to commencement of construction activities. The haul route exhibit shall design delivery routes to minimize the exposure of sensitive land uses or residential dwellings to delivery truck-related noise. Per the County's Cooperative Agreement with the City of Irvine, the designated access roads to the FRB Landfill are I-405, I-5, Sand Canyon Avenue, Portola Parkway and Bee Canyon Access Road. These same roadways will be used by vehicles going to and from the composting operation during both the construction and operational phases of the project.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During construction and operations	OCWR			
(Noise Control PDF & OCM-3) All construction equipment shall use noise-reduction features (e.g., mufflers and engine shrouds) that are no less effective than those originally installed by the manufacturer.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During construction and operations	OCWR			
(Noise Control PDF & OCM-4) Trucks hauling building materials to construction sites can be sources of noise and vibration intrusion if the haul routes pass through residential neighborhoods on streets with bumps or potholes. During both the construction and operational phases of the project, OCWR shall be responsible for repairing the bumps and potholes on Bee Canyon Access Road in order to prevent this additional source of construction and operational noise in residential areas. Bumps and potholes on Portola Parkway and Sand Canyon Avenue are repaired during routine maintenance performed by the City of Irvine.	Issuance of Solid Waste Facility Permit by LEA	Verification by OCWR Composting Facility Superintendent	During construction and operations	OCWR			

1/1111011110111101	71 122 0 2122 1 0 1 22 1	J 11221 0 211 2 2 1 1 0	1 210 0 211 21:2		
(Noise Control PDF & OCM-5) All trucks, windrow turners,	Issuance of Solid	Verification by	During	OCWR	
loaders and any other heavy equipment used during both the	Waste Facility	OCWR	construction and		
construction and operational phases of the project shall be	Permit by LEA	Composting	operations		
operated with properly operating and well-maintained mufflers.		Facility			
		Superintendent			
(Noise Control PDF & OCM-6) Truck drivers shall turn off	Issuance of Solid	Verification by	During	OCWR	
engines when not in use; diesel trucks servicing the project shall	Waste Facility	OCWR	construction and		
not idle for more than five (5) minutes.	Permit by LEA	Composting	operations		
\	,	Facility			
		Superintendent			
(Noise Control PDF & OCM-7) OCWR shall post telephone	Issuance of Solid	Verification by	During	OCWR	
numbers at the entrance of the composting facility to allow	Waste Facility	OCWR	construction and		
members of the public to contact the OCWR composting	Permit by LEA	Composting	operations		
facility superintendent to report noise complaints.	,	Facility			
		Superintendent			
(Noise Control PDF & OCM-8) The construction contractor	Issuance of Solid	Verification by	During	OCWR	
shall locate equipment staging in areas that will create the	Waste Facility	OCWR	construction		
greatest distance between construction-related noise sources and	Permit by LEA	Composting			
most noise-sensitive receptors nearest the project site during all	-	Facility			
project construction.		Superintendent			
(Noise Control PDF & OCM-9) The construction contractor	Issuance of Solid	Verification by	During	OCWR	
shall place all stationary construction equipment so that the	Waste Facility	OCWR	construction		
emitted noise is directed away from the sensitive receptors	Permit by LEA	Composting			
nearest the project site.		Facility			
		Superintendent			
	Transportatio	n			
(Transportation PDF & OCM-1) Trucks going to and	Issuance of Solid	Verification by	During	OCWR	
coming from the composting operation will be required to use	Waste Facility	OCWR	construction and		
the same roadways that waste hauling vehicles use for accessing	Permit by LEA	Composting	operations		
the landfill operation. These authorized roadways include I-		Facility			
405, I-5, Sand Canyon Avenue, Portola Parkway and Bee		Superintendent			
Canyon Access Road.					